



Toonga shearers' quarters, Tarcutta. *PF 1999 photograph*

**WAGGA WAGGA CITY COUNCIL  
RURAL HERITAGE STUDY  
VOLUME 2 : INVENTORY PART 4**

TARCUTTA THE GAP THE ROCK URANQUINTY YARRAGUNDRY

**PETER FREEMAN PTY LTD  
CONSERVATION ARCHITECTS / PLANNERS • CANBERRA**

**AUGUST 2000**

WAGGA WAGGA CITY COUNCIL  
RURAL STUDY  
VOLUME 2 : INVENTORY PART 4

00121

THE RURAL INVENTORY

THE INVENTORY STRUCTURE

Inventory data sheets have been prepared for those buildings, sites or landscape elements of significance which have been identified within the rural areas of the City of Wagga Wagga. In order to present this volume of information in a coherent manner the rural inventory has been ordered into localities, which correspond with the postal addressing system which is to be implemented by the Wagga Wagga City Council.

These localities are as follows, and their boundaries are outlined on the map below:



Map of the Wagga Wagga City Council area, showing localities.  
Source:  
WWCC

## METHODOLOGY

A standard inventory form has been used for the recording of all rural heritage items. This form records the following information:

<b>Name</b>	<i>Name of site/item</i>
<b>Address</b>	<i>Street address</i>
<b>Town/place</b>	<i>Town or area</i>
<b>Locality</b>	<i>Locality determined according to the Wagga Wagga City Council rural address system</i>
<b>Other names</b>	<i>Earlier or informal names</i>
<b>Current heritage listings</b>	<i>Current listing includes the following registers: Australian Heritage Commission National Trust of Australia [NSW] Wagga Wagga City Council Heritage Council of NSW RAIA Register of 20<sup>th</sup> Century Buildings</i>
<b>Related places</b>	
<b>Thematic context</b>	<i>Thematic context drawn from the NSW Historical Themes</i>
<b>Site type</b>	<i>Type of site, ie Church, Hall etc</i>
<b>Property details</b>	<i>Real property description [where known]</i>
<b>Map reference</b>	<i>AMG reference [where property details not available]</i>
<b>Historical background</b>	<i>Drawn from readily available sources; from existing citations; or from this study's Thematic Environmental History</i>
<b>Description</b>	
<b>Statement of significance</b>	
<b>Photograph/Plan</b>	<i>One photograph or plan is included for most entries, extra photo pages are included for some entries.</i>
<b>Sources of information</b>	

## ARRANGEMENT OF THE RURAL INVENTORY ITEMS

The rural inventory has been placed within one volume [Parts 1 to 4], as follows.

### Volume 2 Part 1

Alfredtown	ALF
Ashmont	ASH
Belfraydon	BEL
Big Springs	BIG
Bomen	BOM
Book Book	BOO
Borambula	BOR
Brucedale	BRU
Bulgary	BUL
Burrandana	BUR
Cartwright's Hill	CAR
Charles Sturt Uni	CHA
Collingullie	COL
Currawarna	CUR
Downside	DOW
Euberta	EUB

### Volume 2 Part 2

Eunonyhareenyha	EUN
Forest Hill	FOR
Galore	GAL
Ganmain	GAN
Gregadoo	GRE
Gumly Gumly	GUM
Humula	HUM
Kapooka	KAP
Kyeamba	KYE
Ladysmith	LAD
Lake Albert	LAK
Lockhart	LOC

### Volume 2 Part 3

Mangoplah	MAN
Matong	MAT
Maxwell	MAX
Moorong	MOO
Oberne Creek	OBE
Oura	OUR
Pulletop	PUL
Rowan	ROW

### Volume 2 Part 4 [this volume]

Tarcutta	TAR
The Gap	TGA
The Rock	TRO
Uranquinty	URA
Yarragundry	YAR

## RURAL INVENTORY INDEX

The following list includes all items included within the rural inventory. Those items which are to be found within Part 4 of Volume 2 are in bold type.

ALF 01	Old Glandore Homestead and outbuildings	Alfredtown
ALF 02	The Shanty	Alfredtown
ASH 01	Best family cemetery	Ashmont
BEL 01	Belfrayden silos	Belfrayden
BIG 01	Big Springs [1988 DCP homestead and outbuildings]	Big Springs
BIG 02	Big Springs woolshed and yards	Big Springs
BIG 03	Cox cottage ruin	Big Springs
BIG 04	Livingstone Gully School [former]	Big Springs
BOM 01	Bomen Railway Station	Bomen
BOM 02	Bomen Stationmaster's Residence	Bomen
BOM 03	Brooklyn	Bomen
BOO 01	Book Book Public School site	Book Book
BOO 02	Book Book Station early homestead site	Book Book
BOO 03	Book Book Station gardener's cottage	Book Book
BOO 04	Book Book Station homestead and entrance gates	Book Book
BOO 05	Book Book Station woolshed complex	Book Book
BOO 06	Book Book tennis court	Book Book
BOO 07	Hayshed	Book Book
BOR 01	Tarra Wingee and outbuildings	Borambola
BOR 02	Borambola	Borambola
BOR 03	Borambola Hall	Borambola
BOR 04	Borambola Park outbuildings	Borambola
BOR 05	Borambola woolshed	Borambola
BOR 06	Old Borambola	Borambola
BOR 07	Tennis courts and clubhouse	Borambola
BOR 08	Bungarabee	Lower Tarcutta
BOR 09	Lower Tarcutta settlement site	Lower Tarcutta
BOR 10	Stone culvert	Lower Tarcutta
BOR 11	Lower Tarcutta cemetery	Lower Tarcutta
BOR 12	Remains of former Adelaide Road	Lower Tarcutta
BRU 01	Brucedale hall and tennis courts	Brucedale
BRU 02	Brucedale Public School [former]	Brucedale
BRU 03	Holy Family Chapel	Brucedale
BRU 04	Hopevale	Brucedale
BRU 05	Pine Ridge cottage	Brucedale
BRU 06	Shepherds concrete silos	Shepherds
BUL 01	Bulgary Provisional School [former]	Bulgary
BUR 01	Burrandana Siding building	Burrandana
BUR 02	Burrandana school site and tennis court	Burrandana
BUR 03	Burrandana hall and tennis court	Burrandana
CAR 01	Wattle Vale	Cartwrights Hill
CHA 01	Cobb elevator and granary building foundations	CSU
CHA 02	Former cannery	CSU
CHA 03	Olive trees	CSU
CHA 04	Former Experiment Farm manager's residence	CSU
COL 01	Roman Catholic Church	Collingullie
COL 02	Collingullie playground sign	Collingullie
COL 03	St Margaret's Uniting Church	Collingullie
COL 04	Berryjerry homestead	Collingullie
COL 05	Yarragundry woolshed	Collingullie
COL 06	Sarsfield Park	Collingullie
COL 07	Collingullie Hall	Collingullie
COL 08	Collingullie School	Collingullie
COL 09	Timber bridge	Collingullie
COL 10	Pine tree and fence post	Collingullie
COL 11	Selector's cottage on Piney Grove	Uranquinty
CUR 01	Currawarna Public School	Currawarna

CUR 02	Currawarna Community Centre	Currawarna
CUR 03	Currawarna Cemetery	Currawarna
DOW 01	Downside hall and recreation ground	Downside
DOW 02	St Stephen's Uniting Church	Downside
DOW 03	Downside shooting range	Downside
EST 01	Estella house, outbuildings and stables	Wagga Wagga
EUB 01	Timber and slab building on Riverslie	Euberta
EUB 02	Euberta community centre [former school]	Euberta
EUB 03	Euberta hall, tennis courts and recreation reserve	Euberta
EUB 04	Rathmount	Malebo
EUB 05	Windy Hill pise house	Malebo
EUB 06	Malebo park pise house, well and sawmill [RNE?]	Malebo
EUB 07	Malebo School [former]	Malebo
EUN 01	Kurrajong woolshed and shearers' quarters	Eunonyhareenyha
EUN 02	Hareenyha slab shed	Eunonyhareenyha
EUN 03	Inglebrae	Eunonyhareenyha
EUN 04	Eunonyhareenyha cottage and 1920 cottage	Eunonyhareenyha
EUN 05	Numeralla Park	Eunonyhareenyha
FOR 01	Cowell and Saxon family graves	Forest Hill
FOR 02	Timber railway bridge	Forest Hill
FOR 03	RAAF Base gatehouse	Forest Hill
GAL 01	Arajoel Siding grain silos	Arajoel
GAL 02	Hill Plain blacksmith's shop	Galore
GAL 03	Wagingoberembee graves	Galore
GAL 04	Wagingoberembee log shed	Galore
GAL 05	Church of St Michael's and Angels	Galore
GAL 06	Galore Siding	Galore
GAL 07	Roman Catholic Church	Galore
GAL 08	Galore Hall and tennis courts	Galore
GAL 09	Arajoel Homestead complex	Galore
GAN 01	Ganmurra bridge	Ganmurra
GAN 02	Glen Eith Park stables	Kockibitoo
GAN 03	Kockibitoo School [former]	Kockibitoo
GAN 04	Mangain Reserve shooting range	Mangain
GRE 01	Gregadoo Station complex	Gregadoo
GRE 02	Stone ruin	Gregadoo
GRE 02	Ivy Dale	Gregadoo
GRE 02	Ivy Dale woolshed	Gregadoo
GUM 01	Gumly Gumly homestead	Gumly Gumly
GUM 02	St Ninian's Church	Gumly Gumly
HUM 01	Federation timber residence	Humula
HUM 02	Humula recreation ground and meeting room	Humula
HUM 03	Humula recreation ground entrance gates	Humula
HUM 04	Chinaman's Hill	Humula
HUM 05	Carabost Creek Chinese mine sites	Humula
HUM 06	Cottage	Humula
HUM 07	Humula Hotel ruin	Humula
HUM 08	Tin Shed Hotel ruin	Humula
HUM 09	Railway bridge	Humula
HUM 10	Humula Station	Humula
HUM 11	Humula Station woolshed and fittings	Humula
HUM 12	Former boxing ring	Humula
HUM 13	CWA Rooms [former]	Humula
HUM 14	Humula Hall	Humula
HUM 15	Humula post office	Humula
HUM 16	St Therese Roman Catholic Church	Humula
HUM 17	Union Church	Humula
HUM 18	Humula Cemetery	Humula
HUM 19	Possum Plain woolshed	Humula
HUM 20	Humula Galvin Tennis Club	Humula
HUM 21	Humula Public School	Humula
HUM 22	Cheney graves	Humula
HUM 23	Shockeroo Homestead	Humula
HUM 24	Federation timber cottage	Humula
HUM 25	Butcher shop	Humula

HUM 26	Murraguldrie Public School site	Murraguldrie
HUM 27	William John Nugent grave [relocated]	Umbango
HUM 28	Nugent fences	Umbango
HUM 29	Wooden gate [Umbango village]	Umbango
KAP 01	Kapooka railway bridge	Kapooka
KAP 02	Nissen hut	Kapooka
KYE 01	Kyeamba Police residence / Angel's residence	Kyeamba
KYE 02	Kyeamba South homestead	Kyeamba
KYE 03	Kyeamba Station cemetery	Kyeamba
KYE 04	Kyeamba Station homestead	Kyeamba
KYE 05	Kyeamba Station seed bin	Kyeamba
KYE 06	Kyeamba Station stable and machinery shed	Kyeamba
KYE 07	Kyeamba Station vineyard	Kyeamba
KYE 08	Kyeamba Station wine press and cellar	Kyeamba
KYE 09	Kyeamba Station workmen's quarters	Kyeamba
KYE 10	Vineyard and wine shanty site [Koinglo West]	Kyeamba
KYE 11	Kilgowla Old Post Office site	Kyeamba
KYE 12	Port Phillip Road [south of Kyeamba Station]	Kyeamba
KYE 13	Twisted chimney	Kyeamba
LAD 01	Concrete silos	Ladysmith
LAD 02	Church of Our Lady	Ladysmith
LAD 03	Stationmaster's residence [former]	Ladysmith
LAD 04	St Saviour's Anglican Church	Ladysmith
LAD 05	School residence [former]	Ladysmith
LAD 06	General store and residence	Ladysmith
LAD 07	Ladysmith Memorial Hall	Ladysmith
LAD 08	Railway station, shed, points and siding	Ladysmith
LAD 09	Lothlorien	Ladysmith
LAD 10	Methodist Church	Ladysmith
LAD 11	Public School	Ladysmith
LAK 01	Allonby	Forest Hill
LAK 02	St Peter's Anglican Church	Lake Albert
LAK 03	The Club	Lake Albert
LOC 01	Bullenbong private cemetery	Bullenbong
LOC 02	Brookdale hall and tennis courts	Brookdale
MAN 01	Lutheran Church cemetery	Mangoplah
MAN 02	Lutheran Church site	Mangoplah
MAN 03	General store and residence	Mangoplah
MAN 04	Mangoplah silos and grain storage shed	Mangoplah
MAN 05	Mangoplah Station complex	Mangoplah
MAN 06	Mangoplah Hall	Mangoplah
MAN 07	Mangoplah Public School	Mangoplah
MAN 08	Mangoplah PS former teacher's residence	Mangoplah
MAN 09	Scots Uniting Church	Mangoplah
MAN 10	Mangoplah Hotel	Mangoplah
MAN 11	Store [former] and residence	Mangoplah
MAN 12	Mangoplah cenotaph	Mangoplah
MAN 13	St Michael Archangels Roman Catholic Church	Mangoplah
MAN 14	Mangoplah Recreation Ground	Mangoplah
MAN 15	Kilmonin	Mangoplah
MAT 01	Deepwater homestead and shed complex	Matong
MAT 02	Deepwater woolshed and well	Matong
MAX 01	Gillamagong	Maxwell
MAX 02	Fleetwood and almond orchard	Sandy Creek
MAX 03	Little Sandy Creek slab cottage and woolshed	Sandy Creek
MOO 01	Moorong Station ruins	Moorong
MOO 02	Tobacco kiln	Wagga Wagga
OBE 01	Galvin graves	Oberne
OBE 02	Janey Harvey's cottage and outbuildings	Oberne
OBE 03	Milk can collection box	Oberne
OBE 04	Bardwell family graves	Oberne
OBE 05	Grandpa's Hill and Chinaman's Creek	Oberne
OBE 06	Oberne Hall	Oberne
OBE 07	Oberne House ruin	Oberne
OBE 08	Oberne tennis courts and school site	Oberne

OBE 09	Dellhaven	Oberne
OBE 10	Oberne Valley cultural landscape	Oberne
OBE 11	St Albans Lucas Memorial Church	Westbrook
OBE 12	Westbrook Public School site	Westbrook
OBE 13	Westbrook PMG building	Westbrook
OUR 01	Oura community centre and tennis courts	Oura
OUR 02	Oura Station homestead	Oura
OUR 03	Scots Church	Oura
OUR 04	Brick cottage	Oura
OUR 05	Pise cottage	Oura
PUL 01	Mud brick ruin	Pulletop
PUL 02	Pulletop Siding	Pulletop
PUL 03	Pulletop Station homestead ruin	Pulletop
PUL 04	Pulletop Station manager's cottage [former chapel]	Pulletop
PUL 05	Cressy Farm	Pulletop
PUL 06	Knox Union Church	Pulletop
PUL 07	Wandoo stone cottage	Westby
PUL 08	Railway cutting	Westby
PUL 09	Westby railway station and turntable site	Westby
PUL 10	Westby school site and pise cottage	Westby
PUL 11	Wingelo yards	Westby
PUL 12	Stone ruin	Westby
ROW 01	Rowan	Wagga Wagga
TAR 01	Tennis courts	Keajura
TAR 02	St Columba's Presbyterian Church	Tarcutta
TAR 03	Inflammable liquid store	Tarcutta
TAR 04	Tarcutta Public School	Tarcutta
TAR 05	Cynthia Street corrugated iron cottage	Tarcutta
TAR 06	Cynthia Street slab cottage	Tarcutta
TAR 07	Cynthia Street slab and timber shed	Tarcutta
TAR 08	St Mark's Mate Memorial Church	Tarcutta
TAR 09	St Mark's Mate Memorial Church graves	Tarcutta
TAR 10	Tarcutta Cemetery	Tarcutta
TAR 11	Tarcutta school and residence [former]	Tarcutta
TAR 12 D	Hambledon Homestead	Tarcutta
TAR 13	Hambledon outbuildings	Tarcutta
TAR 14	Tarcutta Inn [former]	Tarcutta
TAR 15	Tarcutta Railway Station complex	Tarcutta
TAR 16	Tarcutta Railway Station complex and former shop	Tarcutta
TAR 17	Tarcutta House	Tarcutta
TAR 18	Elizabeth Nugent grave on 'College Creek'	Tarcutta
TAR 19	Toonga Homestead	Tarcutta
TAR 20	Toonga shearers' quarters	Tarcutta
TAR 21	Wynyard woolshed	Tarcutta
TAR 22	Chinese clearing site	Tarcutta
TAR 23	Edwards Siding, bridge and abandoned railway line	Tarcutta
TAR 24	Split log fence	Tarcutta
TAR 25	Tennis courts, Breaden Sportsground	Tarcutta
TAR 26	Sydney Street corrugated iron shop [former]	Tarcutta
TAR 27	Sydney Street butcher shop	Tarcutta
TAR 28	CWA Hall	Tarcutta
TAR 29	Post office [former]	Tarcutta
TAR 30	Sydney Street house and forme store	Tarcutta
TAR 31	Police Station	Tarcutta
TAR 32	Sydney Street slab house	Tarcutta
TAR 33	St Francis Xavier Roman Catholic Church	Tarcutta
TAR 34	Tarcutta Hotel	Tarcutta
TAR 35	Tarcutta Memorial Hall	Tarcutta
TAR 36	Tarcutta Store/Cafe	Tarcutta
TAR 37	Sydney Street timber store	Tarcutta
TAR 38	Truckies' memorial	Tarcutta
TAR 39	Sydney Street commercial building [fmr CBC bank]	Tarcutta
TAR 40	Brooklyn woolshed	Tarcutta
TAR 41	Umbango Siding	Umbango

TGA 01	Cottee recreation reserve	Cottee
TGA 02	Flowerdale School	Flowerdale
TGA 03	The Gap hall site and tennis courts	The Gap
TGA 04	Tooyal recreation ground	Tooyal
TGA 05	Kittegora school site	Tooyal
TGA 06	Concrete ruin	The Gap
TGA 07	Moreton Bay fig	The Gap
TRO 01	Bonna Vista	The Rock
TRO 02	Briscoe grave site [out of area]	The Rock
TRO 03	Railway gate	The Rock
TRO 04	Old Trunk Road	The Rock
URA 01	School site	Mundowey
URA 02	Kildare cottage	Pearson
URA 03	Old Calmsley	Pearson
URA 04	Wyadra grave site	Pearson
URA 05	Water tower	Uranquinty
URA 06	Uranquinty cemetery	Uranquinty
URA 07	Cenotaph	Uranquinty
URA 08	Liquid Explosives Store and Explosives Store	Uranquinty
URA 09	Uranquinty Reserve	Uranquinty
URA 10	St Patrick's Roman Catholic Church	Uranquinty
URA 11	Uranquinty Hotel	Uranquinty
URA 12	Uranquinty General Store [former]	Uranquinty
URA 13	Uranquinty General Store mail boxes	Uranquinty
URA 14	St Cuthbert's Church of England Church	Uranquinty
URA 15	Trinity Lutheran Church	Uranquinty
URA 16	O'Connor Street weatherboard cottage	Uranquinty
URA 17	Ganawarra, Pearson Street	Uranquinty
URA 18	Memorial Avenue, Pearson Street	Uranquinty
URA 19	Uranquinty Hall	Uranquinty
URA 20	Uranquinty silos	Uranquinty
URA 21	Uranquinty School	Uranquinty
URA 22	Wise grave	Uranquinty
YAR 01	Pomingalarna	Wagga Wagga
YAR 02	Yarragundry School [former]	Yarragundry
YAR 03	Cottage and pise outbuilding	Yarragundry

# Wagga Wagga Heritage Study 1999

---

Name: Tennis Courts Reference No: TAR 01  
Address: Old Hume Highway  
Town/Place Keajura Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Sport

Site Type Tennis

## Property Details

Map Reference Tarcutta 8427-3-N 588 903

## Historical Background

The tennis courts are on the east side of the Old Hume Highway and are accessed via the 'Corona' property. Keajura School was located not far away, south of the Keajura Creek, a site which is now in the middle of the Hume Highway. Jonquils mark the site in Spring. The Keajura Provisional School was opened in 1888 and closed in 1895, being wrecked by a storm in 1896.

## Description

Weatherboard pavilion, with steel portico windows. The courts are adjacent 'Corona' Homestead.

## Statement of Significance

These tennis courts are a reminder of a recreational activity which was important in rural communities during the first half of the 20th century. Local significance.

## Photograph/Plan

## Sources of Information

Ray Davies, Tarcutta



# Wagga Wagga Heritage Study 1999

---

Name: St Columba's Presbyterian Church

Reference No: TAR 02

Address: Argent Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Religion

Site Type Church

Property Details Lot 209

Map Reference Tarcutta 8427-3-N

## Historical Background

The building of the church was instigated by the Allison family, who arrived in Tarcutta in 1929, and by Mr S.S. Whitehead. In 1931 Mr Whitehead gave land for a church site and a contract for the building was given to Mr L. Beattie in February 1932. Mrs S.S. Whitehead laid the foundation stone. The Tarcutta Presbyterian Church was opened and dedicated in November 1932. In 1950 the church was dedicated to the memory of St Columba.


## Description

Well proportioned small rural church. Cement rendered and scored to resemble ashlar. Buttresses divide the side elevations into bays and there are three pointed arch windows to each side. Exposed rafters.

## Statement of Significance

St Columba's is of historical and social significance to the Tarcutta community. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Inflammable Liquid Store  
Address: Bent Street, cnr Cynthia Street  
Town/Place Tarcutta

Reference No: TAR 03  
Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Commerce

Site Type Miscellaneous

Property Details

Map Reference Tarcutta 8427-3-N 671 957

Historical Background

## Description

Fibro cement, concrete block footings. Pole and sleeper loading tray.

## Statement of Significance

Architectural and aesthetic value as a relatively intact example of mid 20th century store shed construction. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Tarcutta Public School

Reference No: TAR 04

Address: Centenary Avenue

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Education

Site Type School

## Property Details

Map Reference Tarcutta 8427-3-N 671 956

## Historical Background

The Tarcutta School was established in 1873, and has occupied this site since 1953. Immediately after World War I on this site the Government provided a nurse and hospital. The nurse's duty was to treat newly settled soldier settler's war wounds and ailments.

## Description

Long low weatherboard building with a central gable-ended projection with three windows and a circular louvred vent. Gable roof is clad with corrugated iron.

## Statement of Significance

Social significance to the community of Tarcutta and district. Local significance.

## Photograph/Plan



## Sources of Information

Ray Davies  
Roger Belling

# Wagga Wagga Heritage Study 1999

---

Name: Corrugated iron cottage

Reference No: TAR 05

Address: Cynthia Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Townships

Site Type House

Property Details Lot 8 DP 758953

Map Reference Tarcutta 8427-3-N 673 958

Historical Background

## Description

CGI cottage, painted in mustard and red. Features include a four panel front door flanked by 12-pane windows, round timber verandah rafters, ogee guttering, sunhood and brick chimney.

## Statement of Significance

Historical and aesthetic significance, and an indication of the diversity of housing construction materials evident in Tarcutta. Local significance.

## Photograph/Plan

## Sources of Information

Jill Morrow



# Wagga Wagga Heritage Study 1999

---

Name: Corrugated iron cottage

Reference No: TAR 05

Address: Cynthia Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---



North elevation

# Wagga Wagga Heritage Study 1999

---

Name: Slab cottage

Reference No: TAR 06

Address: Cynthia Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Townships

Site Type House

Property Details Lot 3 DP 758953

Map Reference Tarcutta 8427-3-N 672 957

Historical Background

## Description

Cream painted slab cottage, with a weatherboard addition to the south end. Weatherboard pediment at front and two 12 pane windows on either side of door. Timber footings.

## Statement of Significance

Historical and aesthetic significance, and an indication of the diversity of housing construction materials evident in Tarcutta. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Slab and timber shed  
Address: Cynthia Street, cnr Spring Street  
Town/Place Tarcutta

Reference No: TAR 07

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context

Site Type

Property Details Lot 5 DP 758953

Map Reference Tarcutta 8427-3-N 675 960

Historical Background

## Description

Slab and timber shed, possibly 1861, at rear of cottage at south-east corner of Cynthia and Spring Streets, Tarcutta. Vertical slabs; the south elevation slabs have been removed to allow car accommodation.

## Statement of Significance

Historical and aesthetic significance as a remnant timber slab outbuilding. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: St Mark's Mate Memorial Church

Reference No: TAR 08

Address: Gresham Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Religion

Site Type Church

Property Details

Map Reference Tarcutta 8427-3-N 671 962

Historical Background

Consecrated 15 November 1902. Memorial tablet reads that the church was 'given' by Maria Mate and her sister Annie Thompson in memory of their parents Thomas Hodges and Maria Mate. Located in an area where the initial development of Tarcutta was located. Around 1890 there was a Union Church in Hay Street. When St Mark's was built it was given to the Presbyterians and during the 1930s moved to a location between Wagga Wagga and Albury.

Description

Church of bonded brick construction with painted roughcast panels. Gabled, timber framed porch. Paired round-headed windows with simple leadlighting. There is a group of three round-headed windows to the east wall. Cypress pine ceiling.

Statement of Significance

Historical, social and aesthetic significance and a fine example of a rural church building and associated cemetery. State significance.

Photograph/Plan



Sources of Information

Mr Ray Davies  
NTA [NSW] Listing [prepared by  
Jill Morrow]

# Wagga Wagga Heritage Study 1999

---

Name:	St Mark's Mate Memorial Church graves	Reference No:	TAR 09
Address:	Gresham Street		
Town/Place	Tarcutta	Suburb/Locality	Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context      Death

Site Type              Cemetery

## Property Details

Map Reference         Tarcutta 8427-3-N 672 962

## Historical Background

The reserve for the cemetery and church was set aside in 1875 and Maria Mate was buried here in 1876. Julia Baasen was the wife of Berry Baasen, a Norwegian also known as 'Jacky Johnston'. Her grave features its original finely detailed timber surround. Because the burials are located to the east and north of the church there is little order in the cemetery layout.

## Description

Cemetery in the adjoining paddock to St Mark's. On the north side of the church are graves for Julia Baasen [1896 and James Waldron [1885]. To the south-east side of the church are commemorated George B.A. Podmore [1989], Maria Mate [1876], Thomas Mate [1894 buried Waverly] and William Henry Mate [1927], and children Donald McGregor [1884] and Emily McGregor [1884].

## Statement of Significance

Historical, social and aesthetic significance and a fine example of a rural church building and associated cemetery. State significance.

## Photograph/Plan



## Sources of Information

Jill Morrow  
Ray Dvies  
Ted Brown

# Wagga Wagga Heritage Study 1999

---

Name: St Mark's Mate Memorial Church graves

Reference No: TAR 09

Address: Gresham Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---



The grave of Julia Baassen with its original timber surround.



Other graves/monuments in the cemetery.



# Wagga Wagga Heritage Study 1999

---

Name: Tarcutta Cemetery

Reference No: TAR 10

Address: Gresham Street [north end]

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Death

Site Type Cemetery

Property Details

Map Reference Tarcutta 8427-3-N 673 966

Historical Background

## Description

A substantial cemetery reserve.

## Statement of Significance

Social significance to the community of Tarcutta and district. Local significance.

## Photograph/Plan



## Sources of Information

Ray Davies

# Wagga Wagga Heritage Study 1999

---

Name:	Tarcutta School Residence	Reference No:	TAR 11
Address:	Gresham Street [south end]		
Town/Place	Tarcutta	Suburb/Locality	Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Education

Site Type School residence

## Property Details

Map Reference Tarcutta 8427-3-N 668 961

## Historical Background

Built by Charles Hardy, a prominent Wagga Wagga district builder, in 1884. Similar in design to the police station

## Description

Victorian Georgian brick residence overlooking Tarcutta Oval. House has two chimneys, CGI roof and verandah. Twelve pane windows to front, with stone sills and timber reveals. There is a modern addition to the rear. Set in the western top part of town, which seems to be the oldest part by number of rubble mounds. Previous school and residence. Evidence of significant building alterations on western elevation and site.

## Statement of Significance

Historical and social significance to the community of Tarcutta and district.

## Photograph/Plan

## Sources of Information

Ray Davies, Tarcutta  
Ted Brown



# Wagga Wagga Heritage Study 1999

---

Name:	Hambledon Homestead	Reference No:	TAR 12 D
Address:	Hume Highway		
Town/Place	Tarcutta	Suburb/Locality	Tarcutta

---

Other Names		Current Heritage Listings
Related Places		AHC [RNE] Reg. NSW SHI 00351
Thematic Context	Pastoralism	
Site Type	Homestead [former]	
Property Details	Lot 37 DP 757255 Parish Umutbee County Wynyard	
Map Reference	Tarcutta 8427-3-N 663 953	

## Historical Background

Hambledon Homestead was one of the earliest buildings in this part of the State. It was originally Umutbee Station, established by Thomas Mate when he began grazing sheep here in 1837. Mate's homestead was halfway between Sydney and Melbourne and he opened a store and inn at the homestead and catered to passing travellers. In 1849 he established the Tarcutta Post Office in the building; the settlement of Tarcutta grew up around Mate's homestead. The homestead burnt down in recent years but the outbuildings remain.

## Description

The building was constructed of vertical slabs and was U-shaped; the northern wing dated from the 1837 period.

## Statement of Significance

Hambledon was one of the earliest buildings in the eastern Riverina and was the first inn, store and Post Office on the Gundagai-Albury road. It had a close association with the early development of the area and with travel between Sydney and Melbourne during several decades of the Colonial period. State significance

## Photograph/Plan



## Sources of Information

Australian Heritage Commission  
Campbell Hawthorn

Hambledon Homestead in 1978.  
*Jill Morrow photograph*

# Wagga Wagga Heritage Study 1999

---

Name:	Hambledon outbuildings	Reference No:	TAR 13
Address:	Hume Highway		
Town/Place	Tarcutta	Suburb/Locality	Tarcutta

---

Other Names		Current Heritage Listings
Related Places		AHC [RNE] Reg. NSW SHI 00351
Thematic Context	Pastoralism	
Site Type	Homestead complex [former]	
Property Details	Lot 37 DP 757255 Parish Umutbee County Wynyard	
Map Reference	Tarcutta 8427-3-N 663 953	

## Historical Background

Hambledon Homestead was one of the earliest buildings in this part of the State. It was originally Tarcutta Station, established by Thomas Mate when he began grazing sheep here in 1837. Mate's homestead was halfway between Sydney and Melbourne and he opened a store and inn at the homestead and catered to passing travellers. In 1849 he established the Tarcutta Post Office in the building; the settlement of Tarcutta grew up around Mate's homestead. The homestead burnt down in recent years but the outbuildings remain.

## Description

The property retains an early brick cottage [possibly the former detached kitchen as has large bread oven], constructed with bricks and mortar prepared on site [pictured below] and various other outbuildings including stables and a washhouse behind the cottage. There is a large Roman Cypress, a well and the remains of an earlier stone washhouse

## Statement of Significance

Hambledon was one of the earliest buildings in the eastern Riverina and was the first inn, store and post office on the Gundagai-Albury road. It had a close association with the early development of the area and with travel between Sydney and Melbourne during several decades of the Colonial period. Local significance

## Photograph/Plan



## Sources of Information

Australian Heritage Commission  
Campbell Hawthorn

# Wagga Wagga Heritage Study 1999

---

Name: Hambledon outbuildings

Reference No: TAR 13

Address: Hume Highway

Town/Place Tarcutta

Suburb/Locality Tarcutta

---



Hambledon stable building



Hambledon, Roman cypress.



Hambledon, remains of stone washhouse.

# Wagga Wagga Heritage Study 1999

---

Name:	Tarcutta Inn [former]	Reference No:	TAR 14
Address:	Hume Highway		
Town/Place	Tarcutta	Suburb/Locality	Tarcutta

---

Other Names Horse & Jockey Inn

Related Places

Thematic Context Commerce

Site Type Hotel

Property Details

Map Reference Tarcutta 8427-3-N 663 954

## Historical Background

This property was part of Thomas Mate's Umutbee run. The inn building was built for Mate by Mr John Smith [later of Kyeamba] in 1836 and a licence was granted in 1839. The complex consisted of a blacksmith's shop to the rear, a store and telegraph office. It was a Cobb & Co. staging post. Mate sold the inn in 1877 after the death of his wife and there were a succession of owners. The former inn is situated on the south bank of the Keajura Creek and is therefore vulnerable to flooding.

## Description

A Colonial Georgian brick building with a series of 12-pane sash windows and solid doors. There are brick chimneys at either ends. The corrugated iron clad roof is hipped and there is a timber post supported encircling verandah. The shingles are extant under the iron. There were originally three doors along the front and one at each end onto the verandah. Some are now changed to windows. There is a cellar underneath and the original flagstones tot he front verandah. Internally converted to commercial catering capability.

## Statement of Significance

Historical, aesthetic and social significance as a the earliest commercial building extant in Tarcutta and a fine example of an early inn in the vernacular building style. State significance.

## Photograph/Plan



## Sources of Information

*Tarcutta School Centenary*, 1973  
NTA [NSW] listing [prepared by Jill Morrow], 1981

# Wagga Wagga Heritage Study 1999

---

Name:	Tarcutta Railway Station complex	Reference No:	TAR 15
Address:	Hume Highway		
Town/Place	Tarcutta	Suburb/Locality	Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context      Transport

Site Type              Railway

## Property Details

Map Reference        Tarcutta 8427-3-N 653 942

## Historical Background

In 1884 the idea of a railway line connecting Wagga Wagga with Tumbarumba was first mooted. Railway planners were sceptical as to its profitability as carriage by bullock dray was cheaper than by rail. Interest in the proposed line was revived in 1910. The line was opened for traffic as far as Humula on 14 May 1917. With a break for the war and after three years of construction the line to Tumbarumba was completed by May 1921. Passenger and freight traffic was discontinued during 1974. The line closed in 1987.

## Description

Disused Wagga Wagga-Tumbarumba Railway Line. The complex comprises: the Comatawa Railway Station, which is in a dilapidated state, weatherboard with a corrugated iron roof; an ablution block with wooden louvres, corrugated iron walls and roof; etc. The complex is situated on the Comatawa Creek-Humula road junction; to the east of the present Hume Highway. It is an intriguing and evocative complex. Located south of Tarcutta.

## Statement of Significance

Railway sites such as this have historical and social significance as important reminders of the role that the railway played in providing isolated rural areas with ready access to markets and services. Local significance.

## Photograph/Plan



## Sources of Information

*A History of Ladysmith and District*, Ladysmith Centenary Committee, 1981  
Mrs Lou Smith  
Mr Ray Davies

# Wagga Wagga Heritage Study 1999

---

Name: Tarcutta Railway complex

Reference No: TAR 15

Address: Hume Highway

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Tarcutta Railway Station complex, rear of station



Remnant points, the surrounding structure has fallen down.



Abluion block.

# Wagga Wagga Heritage Study 1999

Name: Tarcutta Railway Station complex former shop  
Address: Hume Highway  
Town/Place Tarcutta

Reference No: TAR 16  
Suburb/Locality Tarcutta

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Commerce  
Site Type Shop

## Property Details

Map Reference Tarcutta 8427-3-N 653 942

## Historical Background

The railway line from Wagga Wagga to Tumbarumba via Tarcutta was opened for traffic as far as Humula on 14 May 1917. Passenger and freight traffic was discontinued during 1974. The line closed in 1987. This was the Comatawa Store in the early 1920s. When the railway went through there was a push to move the village nearer the railway station but Tarcutta residents preferred to stay on the creek. There was also a railway fettler's cottage nearby. The former shop has for many years been used for woolshed purposes.

## Description

An ochre-painted timber shop, now modified for woolshed use.

## Statement of Significance

Historical and aesthetic significance to the local community as a remnant of the railway era and a remnant of an early timber shopfront. Local significance.

## Photograph/Plan



## Sources of Information

*A History of Ladysmith and District*, Ladysmith Centenary Committee, 1981  
Mrs Lou Smith  
Mr Ray Davies  
Mr Roger Belling

# Wagga Wagga Heritage Study 1999

---

Name: Tarcutta House Reference No: TAR 17  
Address: Hume Highway, cnr Humula Road  
Town/Place Tarcutta Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Pastoralism  
Site Type Homestead complex

## Property Details

Map Reference Tarcutta 8427-3-N 655 944

## Historical Background

Built 1880-1883 for Alfred Mate, a son of T.H. Mate, but believed to have been lived in by T.H. Mate's youngest son William. Alfred Mate had married a Miss Podmore, a publican's daughter, and there is said to have been some conflict over this within the Mate family. The house was possibly used as a rectory for a period prior to 1923 and as a temporary hospital prior to 1933. The property was purchased and occupied by Owen Lloyd Jones [who married a daughter of Alfred Mate] during the 1930s and sold in 1980. The orientation of this house has been changed due to the creek [and road] being redirected during the 1940s to prevent frequent flooding of the Hume Highway.

## Description

A substantial red brick residence with a symmetrical front. There is a timber post supported return verandah to the front elevation with a feature gable over the entrance. The building was constructed in three stages. The building has been sensitively restored.

## Statement of Significance

Historical and aesthetic significance as one of a number of substantial residences constructed by members of the Mate family. Local significance.

## Photograph/Plan



## Sources of Information

*Tarcutta School Centenary*, 1973  
NTA [NSW] listing [prepared by Jill Morrow], 1983  
Keith Swan, *History of Wagga Wagga*, 1970  
Tony Craig

# Wagga Wagga Heritage Study 1999

Name: Tarcutta House

Reference No: TAR 17

Address: Hume Highway, cnr Humula Road

Town/Place Tarcutta

Suburb/Locality Tarcutta



Tarcutta House, west elevation, the timber la



Tarcutta House, SE corner of the house. Th  
original section of the building, it is not kno  
the timber lattice verandah trim on this sec



Tarcutta House, Humula Road frontage.

# Wagga Wagga Heritage Study 1999

---

Name:	Elizabeth Nugent grave on 'College Creek'	Reference No:	TAR 18
Address:	Humula Road		
Town/Place	Tarcutta	Suburb/Locality	Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context      Death

Site Type              Burial site

## Property Details

Map Reference          Yaven Creek 8427-2-N 699 886

## Historical Background

Elizabeth Nugent died in 1864, aged 74 years. She allegedly migrated to Australia with her husband, children, and brother-in-law and family. On arrival her husband went missing so she settled here amongst her husband's family. The Nugent, Tresilian and Murraguldrrie families settled the area at the same time, coming up from the coast in bullock drays. Elizabeth Nugent's cottage was approximately 50 meters east of the grave. It was slab and stone and burnt down in 1939 bushfires and all that remains is a pile of stone. Jim Schofield remembers irises flowering each Spring until the early 1950s at the cottage site.

## Description

A broken stone headstone reads 'Died/J 20 1864/Elizabeth Nugent/ aged 74 years'. Another square stone, set into cement, reads 'Elizabeth Nugent/Born 1790/Died 20.10.1864/ aged 74 years RIP'. [Note the discrepancy in the dates.] The whole is surrounded by lumps of granite and other rocks. A cottonwood polar grows below the grave site on the side of the Umbango Creek.

## Statement of Significance

Historical significance as an early lone grave site of one of the district's pioneer families. Local significance.

## Photograph/Plan



## Sources of Information

Jocelyn Kershaw, College Creek  
Jim Schofield

# Wagga Wagga Heritage Study 1999

Name: Toonga Homestead  
Address: Lower Tarcutta Road  
Town/Place Tarcutta

Reference No: TAR 19  
Suburb/Locality Tarcutta

## Other Names

## Related Places

Thematic Context Pastoralism

Site Type Station complex

## Property Details

Map Reference Mount Adrah 8427-1-S 686 995

## Historical Background

Built 1895 for Alfred Mate, a son of T.H. Mate, by Charles Hardy. It was one of the last dwellings built by the Mate family. Alfred Mate let the property run down after the death of his son in World War I and in 1918 the house and 5,500 acres was purchased by William Browne and Frank Parramore. Frank Parramore died at Toonga on 3 August 1940. The property was later broken up for dairy farms and fat lamb properties. Jack Parramore owned the property until his death in 1980. Later owned by Frasers and currently McDonalds.

## Description

Substantial Federation era residence of Flemish bond face brick [fired on site] and retaining many original features. Internal painting was recently undertaken, to match paint scrapes of original colours. There are 7 bedrooms and numerous marble/timber fireplaces throughout. Surrounding verandah are paved with diamond shaped terracotta tiles. Decorative timber bargeboards and fretwork to the gable ends and timber verandahs with decorative timber brackets. Pebble and dash chimney detailing. Maid's quarters, double dunny, cellar. Large lake to rear.

## Statement of Significance

Historical and aesthetic significance as a fine example of a substantial homestead complex constructed by a member of the Mate family. In near original condition and well maintained. State significance.

## Photograph/Plan



## Sources of Information

*Tarcutta School Centenary*, 1973  
Norm & Jill McDonald  
Ray Davies  
*Daily Advertiser*, 21 October 1995  
and 26 February 1993


# Wagga Wagga Heritage Study 1999

---

Name: Toonga Homestead  
Address: Lower Tarcutta Road  
Town/Place Tarcutta

Reference No: TAR 19  
Suburb/Locality Tarcutta

---



# Wagga Wagga Heritage Study 1999

---

Name: Toonga shearers' quarters

Reference No: TAR 20

Address: Lower Tarcutta Road

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Pastoralism

Site Type Shearers' Quarters

Property Details

Map Reference Coreinbob 8427-4-S 672 998

Historical Background

Built during the Parramore ownership of the property, c1950.

## Description

Situated approximately 2 km west of the Toonga homestead, over a range of hills. The shearers' quarters are of corrugated iron with an iron chimney.

## Statement of Significance

An aesthetically pleasing example of mid twentieth century functional design for rural buildings. Local significance.

## Photograph/Plan

## Sources of Information

Norm & Jill McDonald



# Wagga Wagga Heritage Study 1999

---

Name: Toonga shearers' quarters

Reference No: TAR 20

Address: Lower Tarcutta Road

Town/Place Tarcutta

Suburb/Locality Tarcutta

---



Iron chimney and timber tankstand.

# Wagga Wagga Heritage Study 1999

---

Name: Wynyard woolshed

Reference No: TAR 21

Address: Lower Tarcutta Road

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Pastoralism

Site Type Woolshed

Property Details

Map Reference Mount Adrah 8427-1-S 692 001

Historical Background

The 1905 bushfires destroyed a very large shearing shed on this property, which was later replaced by this shed.

Description

A dark red painted weatherboard clad woolshed, in good condition, with four 4-pane timber windows evenly spaced to the southern elevation and no windows to the north. The gable roof is clad with corrugated iron.


Statement of Significance

An interesting example of a weatherboard shearing shed, in very good condition. Local significance.

Photograph/Plan

Sources of Information

Norm McDonald



# Wagga Wagga Heritage Study 1999

---

Name: Chinese clearing site

Reference No: TAR 22

Address: Mates Gully Road

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Ethnic Influences

Site Type Cultural Landscape

Property Details Portion 260

Map Reference Tarcutta 8427-3-N 641 960

Historical Background

Much of this land was cleared by the Chinese, who cut the stumps off at hip height.

Description

The eastern side of Mates Gully Road has many eucalypt stumps remaining. This photo is taken on Jackson's block which has a Roman pine, a small wooden log bridge, two large stands of pseudoacacia and a pile of stone rubble. According to Trevor Burnett a cottage here was flattened up to 20 years ago.

Statement of Significance

Historical significance as a tangible reminder of the presence of the Chinese in the area many years ago. Local significance.

Photograph/Plan



Sources of Information

Trevor Burnett, Tarcutta

# Wagga Wagga Heritage Study 1999

---

Name: Edwards Siding, bridge and abandoned railway line      Reference No: TAR 23  
Address: Mates Gully Road  
Town/Place: Tarcutta      Suburb/Locality: Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context: Transport

Site Type: Railway

## Property Details

Map Reference: Tarcutta 8427-3-N 644 954 [siding] 615 997 [bridge]

## Historical Background

The idea of a railway line connecting Wagga Wagga with Tumbarumba was first mooted in 1884. Railway planners were sceptical as to its profitability as carriage by bullock dray was cheaper than by rail. Interest in the proposed line was revived in 1910. The line was opened for traffic as far as Humula on 14 May 1917. With a break for the war and after three years of construction the line to Tumbarumba was completed by May 1921. Passenger and freight traffic was discontinued during 1974. The line closed in 1987.

## Description

Timber remains of a platform only. The siding was used to collect milk and cream in tin cans from the surrounding dairy farms. Dairying was once the chief farming practise in the Mates Gully Road area. The bridge is a five pylon viaduct railway bridge on concrete piers to the western side of Mates Gully Road. There is likely to be much of this abandoned railway line extant, this section is easily accessed from Mates Gully Road. A line join is dated 1913.

## Statement of Significance

Railway sites such as this have historical and social significance as important reminders of the role that the railway played in providing isolated rural areas with ready access to markets and services. Local significance.

## Photograph/Plan



## Sources of Information

*A History of Ladysmith and District*, Ladysmith Centenary Committee, 1981  
Monica Burnett

# Wagga Wagga Heritage Study 1999

---

Name: Edwards Siding, bridge and abandoned railway line

Reference No: TAR 23

Address: Mates Gully Road


Town/Place Tarcutta

Suburb/Locality Tarcutta

---



Wagga Wagga to Tumbarumba, railway bridge and abandoned railway line.



# Wagga Wagga Heritage Study 1999

---

Name: Split log fence Reference No: TAR 24  
Address: Mates Gully Road  
Town/Place: Tarcutta Suburb/Locality: Tarcutta

---

Other Names Current Heritage Listings

Related Places

Thematic Context: Pastoralism  
Site Type: Fence  
Property Details: Portion 49 Coreinbob  
Map Reference: Tarcutta 8427-3-N 621 988

## Historical Background

This is the road boundary fence to Portion 49 Coreinbob, on the eastern side of Mates Gully Road.


## Description

A fence utilising hand split hardwood posts, originally threaded with plain wire; barbed wire and netting were added later.

## Statement of Significance

An interesting remnant of an earlier form of fencing, now superseded by modern materials and techniques such as concrete posts and becoming increasingly rare. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Tennis courts, Breaden Sportsground

Reference No: TAR 25

Address: Sydney Road [off]

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Sport

Site Type Tennis

## Property Details

Map Reference Tarcutta 8427-3-N 589 903

## Historical Background

Tennis became popular in the district during the 1920s. Tony Roche is a famous product of Tarcutta. His father ran Country Meats butchers shop on the west side of Sydney Road.

## Description

This tennis court is situated below the old school residence. There is a weatherboard pavilion with louvres on one side and plywood panels on another side.

## Statement of Significance

Social significance to the Tarcutta community. Local significance.

## Photograph/Plan



## Sources of Information

*Tarcutta School Centenary, 1973*

# Wagga Wagga Heritage Study 1999

---

Name: Corrugated iron shop [former]

Reference No: TAR 26

Address: Sydney Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Commerce

Site Type Shop

Property Details

Map Reference Tarcutta 8427-3-N

Historical Background

## Description

Simple early wayside stall [later cottage] with corrugated iron walls and corrugated iron roof and verandahs east and west. There are hinged corrugated iron openings in the west and north walls.

## Statement of Significance

Social and historical significance to the community of Tarcutta. Local significance.

## Photograph/Plan



## Sources of Information

Jill Morrow  
Ray Davies  
Ted Brown

# Wagga Wagga Heritage Study 1999

---

Name: Country Meats

Reference No: TAR 27

Address: Sydney Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Commerce

Site Type Shop

Property Details

Map Reference Tarcutta 8427-3-N 673 962

Historical Background

Business was formerly run by international Australian Tennis Star Tony Roche's father.

Description

Art deco style brick building with concrete wash facade incorporating two shop windows and two doors. There is a verandah to the front elevation. Weatherboard to rear.

Statement of Significance

Aesthetic value as an important element of the streetscape of the main street of Tarcutta. Local significance.

Photograph/Plan

Sources of Information

Ray Davies  
Ted Brown



# Wagga Wagga Heritage Study 1999

---

Name: CWA Hall  
Address: Sydney Street  
Town/Place Tarcutta

Reference No: TAR 28  
Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Social institutions

Site Type CWA

## Property Details

Map Reference Tarcutta 8427-3-N 672 959

## Historical Background

In 1884 this was the site of Mr Andrew Ingram's general store, the first in Tarcutta. In 1932 the CWA was formed by Mrs Arthur Belling and Mrs Hammond. Meetings were initially held in the Memorial Hall and a library was formed. In 1946 the CWA purchased this land from Mr A.A. O'Brien and the building was constructed in 1954/55. Trees of remembrance have been planted in the grounds for past members.

## Description

Weatherboard dado and fibro cement building. Sash windows, corrugated iron roof.

## Statement of Significance

Social significance to the community of Tarcutta and district. Local significance.

## Photograph/Plan



## Sources of Information

*Tarcutta School Centenary, 1973*

# Wagga Wagga Heritage Study 1999

---

Name: Former Post Office

Reference No: TAR 29

Address: Sydney Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Communications

Site Type Post

## Property Details

Map Reference Tarcutta 8427-3-N 668 958

## Historical Background

A post office opened in Tarcutta in 1849 with Thomas Hodges Mate as postmaster. In 1881 both Post Office and Telegraph were housed in the hotel. This building was constructed in 1886 and with alterations served as post office until postal services were moved next door to the Tarcutta General Store [post 1973].

## Description

The former Post Office is a weatherboard building with galvanised iron roof and twelve-pane sash windows. There is a verandah to the front elevation, under the main roof line. Both front doors are obstructed by signage panels.

## Statement of Significance

Historical and social significance to the community of Tarcutta and district. Local significance.

## Photograph/Plan



## Sources of Information

*Tarcutta School Centenary, 1973*  
Ted Brown

# Wagga Wagga Heritage Study 1999

---

Name: House and former store

Reference No: TAR 30

Address: Sydney Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Townships

Site Type House

## Property Details

Map Reference Tarcutta 8421-3-N

## Historical Background

Built in the 1930-40s by Mr Beattie, a relation of Dame Mary Gilmore. He also built the nearby Sydney Road slab house and the Memorial Hall and shops of concrete construction. Some others of his buildings have already been demolished.

## Description

Slab house with galvanised iron hip roof and bullnose verandah. The front door has sidelights and transom, and is flanked by French doors. The slab technique is now rare in urban areas. Most probably constructed using cypress pine. There is a timber weatherboard extension with a front display window and entrance door.

## Statement of Significance

Historical significance as a rare example of the timber slab construction within during the 20th century and an example of the diversity of residential building construction found in Tarcutta. State significance

## Photograph/Plan



## Sources of Information

Ray Davies  
Jill Morrow  
Ted Brown  
Lou Smith

# Wagga Wagga Heritage Study 1999

---

Name: House and former store


Reference No: TAR 30

Address: Sydney Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---



Detail of slab construction, side elevation.

# Wagga Wagga Heritage Study 1999

---

Name: Police Station

Reference No: TAR 31

Address: Sydney Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Law and order

Site Type Police

## Property Details

Map Reference Tarcutta 8427-3-N 669 957

## Historical Background

Believed to have been built by Charles Hardy, a prominent Wagga Wagga builder during the 1890s. Similar to school residence.

## Description

Red brick building with many later additions, including the unsympathetic enclosing of the front verandah.

## Statement of Significance

Social significance to the community of Tarcutta and district. Local significance.

## Photograph/Plan

## Sources of Information

Ray Davies



# Wagga Wagga Heritage Study 1999

---

Name: Slab house

Reference No: TAR 32

Address: Sydney Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Townships

Site Type House

Property Details

Map Reference Tarcutta 8427-3-N

Historical Background

Built in the 1930-40s by Mr Beattie, a relation of Dame Mary Gilmore. He also built the nearby Sydney Road slab house and the Memorial Hall and shops of concrete construction. Some others of his buildings have already been demolished.

Description

Slab house with galvanised iron hipped roof and bullnose verandah and three brick chimneys on the north elevation. Weatherboards conceal the footings. New aluminium windows and new front door.

Statement of Significance

Historical significance as a rare example of the timber slab construction within during the 20th century and an example of the diversity of residential building construction found in Tarcutta. Local significance.

Photograph/Plan

Sources of Information

Ray Davies



# Wagga Wagga Heritage Study 1999

---

Name: St Francis Xavier Roman Catholic Church

Reference No: TAR 33

Address: Sydney Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Religion

Site Type Church

## Property Details

Map Reference Tarcutta 8427-3-N 672 959

## Historical Background

The land for this church was donated by John Archer many years before the building was constructed. Date of construction unknown.

## Description

Weatherboard church with three timber lancet windows on either side. Corrugated galvanised iron roof and decorative timber bargeboards. There is a porch to the front elevation and an addition to the north side at the rear.

## Statement of Significance

Social significance to the Roman Catholic community of Tarcutta and district. Local significance.

## Photograph/Plan

## Sources of Information

*Tarcutta School Centenary, 1973*



# Wagga Wagga Heritage Study 1999

---

Name: Tarcutta Hotel  
Address: Sydney Street  
Town/Place Tarcutta

Reference No: TAR 34  
Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Commerce

Site Type Hotel

## Property Details

Map Reference Tarcutta 8427-3-N 667 957

## Historical Background

Built c1940-1950

## Description

Art Deco style two storey hotel, with the beer garden to the rear overlooking the Breaden oval. There is a recessed balcony over the central entrance and Art Deco lettering.

## Statement of Significance

Social and historical significance and an important element in the main street of Tarcutta. Local significance.

## Photograph/Plan

## Sources of Information



# Wagga Wagga Heritage Study 1999

---

Name: Tarcutta Memorial Hall

Reference No: TAR 35

Address: Sydney Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Events

Site Type Memorial hall

## Property Details

Map Reference Tarcutta 8427-3-N 669 958

## Historical Background

Before the present hall was built there was one in Cynthia Street. When some money had been raised to build the Memorial Hall, the iron and flooring were bought and this temporary hall was built with the material. It was called the 'Iron Hall'. This hall was built of concrete construction by Mr Beattie in 1928.

## Description

Stuccoed cement front elevation to building; new corrugated galvanised iron roof. High louvred windows to south elevation. The front elevation is symmetrical, with two windows and two marble honour rolls, all with matching window hoods, a decorative element repeated over the entrance door.


## Statement of Significance

Historical and social significance to the community of Tarcutta and district, and an important element in the main street of Tarcutta. Local significance.

## Photograph/Plan

## Sources of Information

*Tarcutta School Centenary, 1973*



# Wagga Wagga Heritage Study 1999

---

Name:	Tarcutta Store	Reference No:	TAR 36
Address:	Sydney Street		
Town/Place	Tarcutta	Suburb/Locality	Tarcutta

---

Other Names Mackie Bros Merchants Current Heritage Listings

## Related Places

Thematic Context Commerce

Site Type Store

## Property Details

Map Reference Tarcutta 8427-3-N 669 958

## Historical Background

Mackie Brothers established their business in 1911, and built this building in 1926.

## Description

Federation free classical style brick building with six timber louvred rectangular windows on each side and a verandah to the front elevation. Historical signage painted over on the front.


## Statement of Significance

Historical and social significance to the Tarcutta township and a popular stopping place for the truckies using the Hume Highway. The building is an important element in the streetscape of Tarcutta. Local significance.

## Photograph/Plan

## Sources of Information

*Tarcutta School Centenary, 1973*



# Wagga Wagga Heritage Study 1999

---

Name: Timber store  
Address: Sydney Street  
Town/Place Tarcutta  
Reference No: TAR 37  
Suburb/Locality Tarcutta

---

Other Names Kirks General Store Current Heritage Listings

## Related Places

Thematic Context Commerce

Site Type Store

## Property Details

Map Reference Tarcutta 8427-3-N 672 958

## Historical Background

This was Bill Breaden's bicycle shop late 20th century. Mr Breaden was very involved in sport in the town [the oval is named after him] and also drove the school bus. Bus was parked in open shed area to the south of store.

## Description

A gable-fronted shopfront, facing onto Tarcutta's main street [east side of Sydney Road]. Timber post supported verandah to front elevation.

## Statement of Significance

Social significance to the community of Tarcutta. Local significance.

## Photograph/Plan



## Sources of Information

Ted Brown

# Wagga Wagga Heritage Study 1999

---

Name: Truckies Memorial

Reference No: TAR 38

Address: Sydney Street

Town/Place Tarcutta

Suburb/Locality Tarcutta

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Transport

Site Type Memorial

Property Details

Map Reference Tarcutta 8427-3-N 670 957

Historical Background

Erected during the 1990s


## Description

This memorial commemorates all the truckies who have died in road accidents throughout Australia. Located to the corner of the park in the main thoroughfare. Comprises series of engraved black marble panels placed on a curving brick wall.

## Statement of Significance

Social significance to the trucking community. National significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Commercial building Reference No: TAR 39  
Address: Sydney Street, cnr Hay Street  
Town/Place Tarcutta Suburb/Locality Tarcutta

---

Other Names Commercial Banking Co. of Sydney Current Heritage Listings

## Related Places

Thematic Context Commerce

Site Type Banking

## Property Details

Map Reference Tarcutta 8427-3-N 672 960

## Historical Background

The Commercial Banking Company of Sydney Ltd first established its branch in Tarcutta in October 1911, on the site presently occupied by the Mobil Service Station. The branch closed in 1914 but reopened in 1923 and this building was erected in 1926. The branch closed in 1974.

## Description

Federation style stuccoed brick and timber building with a gable fronted shop facing the Sydney Street and an attached residence with lattice-enclosed verandah fronting Hay Street.

## Statement of Significance

Historical and social significance to the community of Tarcutta and district. Local significance.

## Photograph/Plan

## Sources of Information

*Tarcutta School Centenary, 1973*



# Wagga Wagga Heritage Study 1999

---

Name: Brooklyn woolshed  
Address: Toonga Settlement Road, cnr Hume Highway  
Town/Place Tarcutta

Reference No: TAR 40  
Suburb/Locality Tarcutta

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Pastoralism

Site Type Woolshed

## Property Details

Map Reference Mount Adrah 8427-1-S 693 993

## Historical Background

This is the original Toonga Station woolshed.

## Description

Situated on a high bank above the Hume Highway. The western elevation is of slab construction, the other three elevations are corrugated iron. The building sits on log stumps. The roof is of corrugated iron.

## Statement of Significance

The woolshed is important for its association with the formerly extensive Toonga Station, and is a landmark to travellers along the Hume Highway. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

Name: Umbango Siding

Reference No: TAR 41

Address: Nugents Road

Town/Place Umbango

Suburb/Locality Tarcutta

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Transport

Site Type Railway

## Property Details

Map Reference Oberne 8427-2-S 696 841

## Historical Background

The idea of a railway line connecting Wagga Wagga with Tumbarumba was first mooted in 1884. Railway planners were sceptical as to its profitability as carriage by bullock dray was cheaper than by rail. Interest in the proposed line was revived in 1910. The line was opened for traffic as far as Humula on 14 May 1917. With a break for the war and after three years of construction the line to Tumbarumba was completed by May 1921. Passenger and freight traffic was discontinued during 1974. The line closed in 1987.


## Description

The visible remains of the siding are concrete piers and a bank of earth. A fence line 10 metres from the concrete piers, on the road side, has the remains of a railway gate hanging on hinges from a gate post.

## Statement of Significance

Railway sites such as this have historical and social significance as important reminders of the role that the railway played in providing isolated rural areas with ready access to markets and services. Local significance.

## Photograph/Plan



## Sources of Information

Fred Smith  
Roger Belling  
Jim Schofield

# Wagga Wagga Heritage Study 1999

---

Name:	Cottee recreation reserve	Reference No:	TGA 01
Address:	Cottee Road and Warren Church Road		
Town/Place	Cottee	Suburb/Locality	The Gap

---

Other Names

Current Heritage Listings

Related Places

Thematic Context      Sport

Site Type              Recreation reserve

Property Details

Map Reference        Coolamon 8328-S 104 314

Historical Background

## Description

This recreation reserve is now covered with pine regrowth. There is a concrete cricket pitch and the ruins of a refreshment booth and two dunnies.

## Statement of Significance

The site is of historical and social significance as a former focus for community leisure and sport activities. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Flowerdale School

Reference No: TGA 02

Address: Flowerdale Road

Town/Place Flowerdale

Suburb/Locality The Gap

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Education

Site Type School

Property Details

Map Reference Coolamon 8328-S 251 318

Historical Background

## Description

This timber school building is typical of the rural school buildings constructed c1920s. It has three large 12-pane windows to the south elevation and a sheltered entrance to the north elevation. The school lettering can be discerned high up on the eastern elevation and there are two remnant water tanks and a further remnant tankstand.

## Statement of Significance

Unused former schools such as this are poignant reminders of the once thriving communities which were formerly scattered throughout the region. Historical, social and aesthetic significance. Local significance.

## Photograph/Plan

## Sources of Information



# Wagga Wagga Heritage Study 1999

---

Name: Flowerdale School

Reference No: TGA 02

Address: Flowerdale Road

Town/Place Flowerdale

Suburb/Locality The Gap

---



Flowerdale School, east elevation. The name can just be made out up high on the gable.

# Wagga Wagga Heritage Study 1999

---

Name: The Gap hall site and tennis courts  
Address: Downside Road and Gap Hall Road  
Town/Place The Gap

Reference No: TGA 03  
Suburb/Locality The Gap

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Cultural site/Sport

Site Type Hall/tennis

## Property Details

Map Reference Coolamon 8328-S 248 283

## Historical Background

## Description

There were originally three tennis courts, a hall and an oval on this site. The hall was demolished at least 30 years ago. The site is now used for grazing purposes.

## Statement of Significance

The site is of historical and social significance as a former focus for community leisure and sport activities. Local significance.

## Photograph/Plan

## Sources of Information



# Wagga Wagga Heritage Study 1999

---

Name: The Gap hall site and tennis courts  
Address: Downside Road and Gap Hall Road  
Town/Place The Gap

Reference No: TGA 03

Suburb/Locality The Gap

---



Former tennis courts, hall site and recreation ground, The Gap.

# Wagga Wagga Heritage Study 1999

---

Name: Umbango Siding

Reference No: TAR 41

Address: Nugents Road

Town/Place Umbango

Suburb/Locality Tarcutta

---



Umbango siding, remains of gate



The railway line embankment snakes away from the Umbango Siding.

# Wagga Wagga Heritage Study 1999

---

Name: Tooyal recreation ground

Reference No: TGA 04

Address: The Gap Road

Town/Place The Gap

Suburb/Locality The Gap

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Sport

Site Type Recreation ground

Property Details

Map Reference Coolamon 8328-S 235 275

Historical Background

## Description

The Tooyal recreation ground is no longer in use. There remains a concrete cricket pitch and a ruinous hall building.

## Statement of Significance

The site is of historical and social significance as a former focus for community leisure and sport activities. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Kittegora school site  
Address: Kittegora School Road  
Town/Place Tooyal

Reference No: TGA 05  
Suburb/Locality The Gap

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Education

Site Type School

## Property Details

Map Reference Coolamon 8328-S 148 355

## Historical Background

## Description

This site comprises perimeter plantings of kurrajongs and a row of [Photinia robusta] exotic species to the north elevation, the remains of two small rock gardens, brick scatters, the remains of a tennis court and the remains of a post and wire fence.

## Statement of Significance

This former schools such is a poignant reminder of the once thriving communities which were formerly scattered throughout the region. Historical and social significance. Local significance.

## Photograph/Plan

## Sources of Information



# Wagga Wagga Heritage Study 1999

---

Name: Concrete ruin  
Address: The Gap Road  
Town/Place Tooyal

Reference No: TGA 06

Suburb/Locality The Gap

---

Other Names

Current Heritage Listings

Related Places

Thematic Context

Site Type

Property Details

Map Reference Coolamon 8328-S 161 281

Historical Background

## Description

Substantial ruin. Walls are concrete scored to resemble ashlar below window height and to the rear elevation and with pebble render above. Hip roof is clad with cgi. Stumps are pine tree logs, floor is timber and ceilings are moulded plaster sheet. There are concrete moulded skirting. The residence features a large ballroom. It has been extensively vandalised and termites are present. At the roadside nearby there is a very large Moreton Bay fig tree.

## Statement of Significance

Historical and aesthetic significance and something of a local landmark. Local significance.

## Photograph/Plan

## Sources of Information



# Wagga Wagga Heritage Study 1999

---

Name: Moreton Bay fig

Reference No: TGA 07

Address: The Gap Road

Town/Place Tooyal

Suburb/Locality The Gap

---

Other Names

Current Heritage Listings

Related Places

Thematic Context

Site Type

Property Details

Map Reference Coolamon 8328-S 161 281

Historical Background

## Description

A very large specimen of a Moreton Bay fig, presumed to be associated with the nearby ruin.

## Statement of Significance

Significant as a particularly fine specimen of Moreton Bay fig tree in the Wagga Wagga region. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Bonna Vista

Reference No: TRO 01

Address: Burkes Creek Road

Town/Place The Rock

Suburb/Locality The Rock

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Pastoralism

Site Type House

## Property Details

Map Reference The Rock 8327-3-N 160 957

## Historical Background

Said to be the original Kohlhagen homestead.

## Description

Situated on the north bank of Burke's Creek, a pise residence with an encircling bullnose verandah. The roof is clad with corrugated iron. There are 4-pane windows, but marks on the wall evidence French doors. A breezeway between the rear kitchen building and the front house has been enclosed.

## Statement of Significance

Historical and aesthetic significance as a relatively intact and comparatively untouched settlers residence. Local significance.

## Photograph/Plan

## Sources of Information

Jenny Garnsey, Bonna Vista



# Wagga Wagga Heritage Study 1999

---

Name: Briscoe grave site  
Address: Collingullie Road  
Town/Place: The Rock

Reference No: TRO 02

Suburb/Locality: The Rock

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context: Death

Site Type: Burial site

## Property Details

Map Reference: The Rock 8327-3-N 106 975

## Historical Background

This burial site is possibly just out of the study area.


## Description

Situated on the western roadside of the Collingullie Road, on the north bank of Burkes Creek. The marble plaque is inscribed 'Sacred to the Memory of Arthur, youngest son of E. & H.H. Briscoe. Born Sept 10 1892. Died Oct 2nd 1893. Tho' lost to sight to memory dear.' There is a small granite headstone with marble plaque fixed to its east face. Surrounded by white painted cast iron fence with stone supports.

## Statement of Significance

This child's grave is a poignant reminder of the hardships of life in the country during the 19th century. Aesthetic significance. Local significance.

## Photograph/Plan



## Sources of Information

Ross Scott

# Wagga Wagga Heritage Study 1999

---

Name: Railway Gate

Reference No: TRO 03

Address: Old Trunk Road

Town/Place The Rock

Suburb/Locality The Rock

---

Other Names

Current Heritage Listings

Related Places

Thematic Context

Site Type

Property Details

Map Reference The Rock 8327-3-N 139 988

Historical Background

In 1880 the railway connection between Bomen and Albury was opened, over a recognised distance of 10 miles [16 kilometres] between the settlements. The gate is situated fronting the Old Trunk Road at 90° to the nearby Main Southern Railway line.


Description

Timber framed gate with three metal bars, reinforcing metal cross-bar, brackets and latch. Mature fruit trees are on the site.

Statement of Significance

An interesting remnant of an earlier railway era. Local significance.

Photograph/Plan



Sources of Information

Uranquinty Public School  
Centenary  
History of Wagga Wagga, Keith  
Swan

# Wagga Wagga Heritage Study 1999

---

Name: The Old Trunk Road

Reference No: TRO 04

Address: Olympic Way [off]

Town/Place The Rock

Suburb/Locality The Rock

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Transport

Site Type Road

## Property Details

Map Reference The Rock 8327-3-N 135 985

## Historical Background

The new surveyed road from Wagga Wagga to 'Hanging' Rock in 1880 met Burkes Creek on either side, vehicles crossing wherever the drivers thought they could cross without getting bogged.

## Description

Unable to access this site, which is located to the west of the present Burkes Creek bridge crossing, however appears to be closed off and redirected part of Old Trunk Road/ water course. The road adjoins the late 20th century property 'Rossmore', and is marked on the map as a closed road.

## Statement of Significance

This evidence of the old trunk road between Wagga Wagga and The Rock is of historical significance as a remnant of an earlier, more challenging network of transport routes, prior to the construction of proper roads and bridges. Local significance.

## Photograph/Plan



## Sources of Information

William A. Bayley, *Land Galore*,  
Lockhart Shire Council, 1979  
Ross Scott

# Wagga Wagga Heritage Study 1999

---

Name: School site

Reference No: URA 01

Address: Uranquinty-Cross Road

Town/Place Mundowry

Suburb/Locality Uranquinty

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Education

Site Type School

## Property Details

Map Reference Uranquinty 8327-4-S 123 098

## Historical Background

Former location of the South Collingullie Public School and a tennis court. Both removed at least 40 years ago.

## Description

Several brick particles scattered around the site. The perimeter is planted with mature peppercorn trees.

## Statement of Significance

Historical and social significance to the local community. Local significance.

## Photograph/Plan



## Sources of Information

Kel Jenkins  
Kath McGeaghie

# Wagga Wagga Heritage Study 1999

---

Name: Kildare cottage  
Address: Old Station Road  
Town/Place: Pearson

Reference No: URA 02  
Suburb/Locality: Uranquinty

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context: Pastoralism

Site Type: Ruin

## Property Details

Map Reference: The Rock 8327-3-N 209 989

## Historical Background

Original dwelling of Thomas Lothian Rodham who arrived in the Wagga Wagga district in 1899 and shortly after built this two room cottage. A verandah surrounded it and it is said that to keep his children occupied on a Sunday he planted an extensive orchard around the house. Still in Rodham ownership.

## Description

A simple pise cottage with a corrugated iron gable roof.

## Statement of Significance

Historical and social significance as a remnant of a simple early cottage. Local significance.

## Photograph/Plan



## Sources of Information

Judy Rodham

# Wagga Wagga Heritage Study 1999

---

Name: Old Calmsley Reference No: URA 03  
Address: Old Station Road [off]  
Town/Place Pearson Suburb/Locality Uranquinty

---

Other Names Current Heritage Listings

Related Places

Thematic Context Pastoralism

Site Type House

Property Details

Map Reference The Rock 8327-3-N 205 987

Historical Background

Built by Eric Sebels. Bought by Mr Dengate senior from Jim Milne 1920s. Was empty for a number of years before the present owner took it over. Supposed to include former Temora Railway Station refreshment counter.

Description

Substantial Federation era pise residence with a corrugated iron hip roof and a gable ended front projection featuring decorative half timbering. Timber post supported return verandah; windows have window hoods. Recently painted yellow.

Statement of Significance

Historical and aesthetic significance as a fine Federation era residence. Local significance.

Photograph/Plan



Sources of Information

Sister Frances [nee Dengate]

# Wagga Wagga Heritage Study 1999

---

Name: Old Calmsley  
Address: Old Station Road [off]  
Town/Place Pearson

Reference No: URA 03  
Suburb/Locality Uranquinty

---



Old Calmsley

# Wagga Wagga Heritage Study 1999

---

Name: Wyadra Grave Site  
Address: South Boundary Road  
Town/Place: Pearson

Reference No: URA 04  
Suburb/Locality: Uranquinty

---

Other Names

Current Heritage Listings

Related Places

Thematic Context

Site Type

Property Details

Map Reference: Uranquinty 8327-4-S 151 064

Historical Background

The grave is probably that of children of the original selection on the hillside, as its marble plaque bears the inscription 'Sacred to the memory of the infant boys of E.W.C. & U.B. Bennett, who died 3rd Oct 1897 & 17 April 1898'.

Description

Small brick and concrete grave, with an inset marble plaque. Located in a paddock and open to stock.

Statement of Significance

Historical significance and an evocative reminder of the hardships of rural life during the 19th century. Local significance.

Photograph/Plan



Sources of Information

Mrs. I Klimpsch

# Wagga Wagga Heritage Study 1999

---

Name: Water tower  
Address: Best Street, cnr Uranquinty Street  
Town/Place Uranquinty  
Reference No: URA 05  
Suburb/Locality Uranquinty

---

Other Names  
Current Heritage Listings  
Related Places  
Thematic Context Utilities  
Site Type Water  
Property Details  
Map Reference Uranquinty 8327-4-S 226 057  
Historical Background


## Description

Large concrete water tank atop a reinforced concrete stand.

## Statement of Significance

Aesthetic significance as a town landmark.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Uranquinty Cemetery  
Address: Churches Plain Road [off]  
Town/Place Uranquinty

Reference No: URA 06  
Suburb/Locality Uranquinty

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Death

Site Type Cemetery

Property Details

Map Reference

Historical Background

## Description

Large, fairly isolated plot with representations of families from the late 19th and twentieth centuries interred there. Divided into denominations and well maintained. On the northern outskirts of the town.

## Statement of Significance

Historical and social significance to the community of Uranquinty and district. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Cenotaph Reference No: URA 07  
Address: Connorton Street  
Town/Place Uranquinty Suburb/Locality Uranquinty

---

Other Names Current Heritage Listings

Related Places

Thematic Context Events

Site Type Memorial

Property Details

Map Reference

Historical Background

A large number of young men from the district, both married and single, enlisted for World War I. At the end of the war the men were welcomed home at a public function in the hall and each man presented with a gold watch. Later the cenotaph was erected in remembrance. Mrs W. Fry Stone officially unveiled the memorial. Trees were planted in Pearson Street, one for each soldier who enlisted. Fourteen men were killed in World War I and 2 in World War II.


Description

Stone obelisk with black marble plaque. Located on the perimeter of the village.

Statement of Significance

Social significance to the community of Uranquinty and district.

Photograph/Plan



Sources of Information

*Uranquinty Public School  
Centenary, 1880-1980*

# Wagga Wagga Heritage Study 1999

---

Name:	Liquid Explosives Store and Explosives Store	Reference No:	URA 08
Address:	Hanging Rock Road		
Town/Place	Uranquinty	Suburb/Locality	Uranquinty

---

Other Names	RAAF School [former] then Migrant Centre	Current Heritage Listings
Related Places		
Thematic Context	Migration/Defence	
Site Type	Migrant camp/Flying school	
Property Details		
Map Reference	Uranquinty 8327-4-S 186 045	

## Historical Background

Built on what is now L & J Lewington's property 'Churchill Square', made famous by the production of prize-winning wheat crops. The RAAF School at Uranquinty commenced construction in September 1941. Pilots were trained in Wirraway aircraft. Most pilots were transferred to Point Cook in 1947 and from 1948 until 1952 it was used as a Migrant Camp as part of Australia's post-war immigration scheme. From 1952 until 1958 pilots were trained here for the Korean War. The base was closed down in 1958 and operations were transferred to Point Cook. Mr L. Lewington purchased the property at auction in 1964.

## Description

The Liquid Explosives Store [pictured below] is a brick building with gable ended walls [forming parapets] at either end and a corrugated iron roof. There are bands of horizontal windows with frosted glass. The Explosives Store [pictured over] is of brick and timber with a hip roof supported on timber brackets. Otherwise the site is mass of piles of debris and concrete slabs. The hangar shelters farm machinery.


## Statement of Significance

Historical and social significance as a remnant of the RAAF School 1941-1947 and 1952-1958] and Migrant Camp [1948-1952] which were located here. Both the Flying School and Migrant Camp operated independently to the town but stimulated the community financially and socially. State significance.

## Photograph/Plan

## Sources of Information

Jenny Lewington  
*Uranquinty Public School  
Centenary, 1880-1980*



# Wagga Wagga Heritage Study 1999

---

Name: Liquid Explosives Store and Explosives Store

Reference No: URA 08

Address: Hanging Rock Road

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

Former RAAF Flying School Explosives Store.



# Wagga Wagga Heritage Study 1999

---

Name: Uranquinty Reserve

Reference No: URA 09

Address: Hanging Rock Road

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

Other Names

Current Heritage Listings

Related Places

Thematic Context

Site Type

Property Details

Map Reference Uranquinty 8327-4-S 208 065

Historical Background

This was the original Uranquinty Public School site, prior to construction of the main Sydney-Melbourne railway. The original school was known as the Sandy Creek School and was situated on 2 acres of land approximately 2.5 km west of Uranquinty. The site, which was then part of the Pomingalarna run, was purchased by the Department of Education in 1878. A brick school and attached residence opened in 1880. The original doorstep is now located at the present Uranquinty Public School. The dirt track the site fronts was the main road that went north through Kapooka to Wagga Wagga and south to The Rock. Nominated Crown Reserve.

Description

A secluded site with a collection of old building debris littering the site. There is a large concrete well and a corrugated iron and timber pavilion shelter.

Statement of Significance

Historical significance to the Uranquinty and district community. Local significance.

Photograph/Plan



Sources of Information

*Uranquinty Public School Centenary, 1880-1980*

# Wagga Wagga Heritage Study 1999

---

Name: St Patrick's Roman Catholic Church

Reference No: URA 10

Address: Morgan Street

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Religion

Site Type Church

## Property Details

Map Reference Uranquinty 8327-4-S 223 053

## Historical Background

Built at the southern end of Morgan Street near the Bridge Street corner during the early 1920s. Mass celebrated on the second and fourth Sundays of the month with the Priest coming from St Michael's Cathedral in Wagga Wagga.

## Description

A red brick church with a steeply pitched gable roof with exposed rafters. Features include buttresses and timber lancet windows. White painted render detailing to the buttresses and window heads. There has been a sympathetic extension to the rear corner.

## Statement of Significance

Historical and social significance to the Roman Catholic community of Uranquinty and district. Local significance.

## Photograph/Plan



## Sources of Information

Uranquinty Public School  
Centenary 1880-1980

# Wagga Wagga Heritage Study 1999

---

Name: Uranquinty Hotel

Reference No: URA 11

Address: Morgan Street

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Commerce

Site Type Hotel

## Property Details

Map Reference Uranquinty 8327-4-S 226 055

## Historical Background

Built in the 1880s by William and C. Jayne Hardiman. Extensions and renovation carried out over the years by its many owners.


## Description

Long low building with a prominent central gable projection featuring decorative half timbering to the gable end. The hip roof is clad with corrugated iron. There are a series of doors and windows along the front elevation and a front verandah to either side of the projection.

## Statement of Significance

The hotel forms an important community focus and is an attractive element in the main street of Uranquinty. Local significance.

## Photograph/Plan



## Sources of Information

*Uranquinty Public School Centenary, 1880-1980*

# Wagga Wagga Heritage Study 1999

Name: Uranquinty General Store [former]  
Address: Morgan Street, cnr Uranquinty Street  
Town/Place Uranquinty

Reference No: URA 12  
Suburb/Locality Uranquinty

## Other Names

## Current Heritage Listings

Related Places Post Boxes  
Thematic Context Commerce  
Site Type Store

## Property Details

Map Reference Uranquinty 8327-4-S 228 056

## Historical Background

This was originally a bakery; the bakehouse still stands at the rear of the store. The last bread was baked here during the 1960s by Sam Castle. The Post Office operated within this formerly bustling General Store. It has closed this year and the business and post office is conducted in a combined store and petrol station next door.

## Description

Brick construction with a corrugated iron roof and an awning verandah. There is a fixed timber bench on the footpath to the front of the building.

## Statement of Significance

This former general store was until recent times the focus of the Uranquinty community and is of historical and social significance. Local significance

## Photograph/Plan



## Sources of Information

Uranquinty Public School  
Centenary, 1880-1980

# Wagga Wagga Heritage Study 1999

---

Name: Uranquinty General Store [former] post boxes

Reference No: URA 13

Address: Morgan Street, cnr Uranquinty Street

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

## Other Names

## Current Heritage Listings

Related Places General Store [former]

## Thematic Context

## Site Type

## Property Details

Map Reference Uranquinty 8327-4-S 228 056

## Historical Background

Private mail boxes, thirty in number. Postal facilities in the form of a receiving office opened here in 1880. The railway station was upgraded 1899 and served as an unofficial post office. The endeavours of the community to establish an official post office have been frustrated and the post office has moved as an adjunct to other businesses. It is presently incorporated in the new general store/petrol station.


## Description

Filigree-fronted mail boxes. The top half is solid metal to accommodate a keyhole. The mailboxes are located on the front wall of the former general store, beneath the awning verandah.

## Statement of Significance

This former general store and post office was until recent times the focus of the Uranquinty community. The post boxes are of historical and aesthetic significance. Local significance.

## Photograph/Plan



## Sources of Information

*Uranquinty Public School Centenary, 1880-1980*

# Wagga Wagga Heritage Study 1999

---

Name: St Cuthbert's Church of England Church

Reference No: URA 14

Address: O'Connor Street

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Religion

Site Type Church

## Property Details

Map Reference Uranquinty 8327-4-S 227 054

## Historical Background

This building replaced an earlier timber church built on land donated by Mr Rod Hoare of Wagga Wagga on the western side of the village in 1895. Other denominations used the church until their churches were built and the of church was used as a house for many years. The Spaul family donated the land for this church, on the eastern side of the village. Volunteers helped gather material and lay foundations. The foundation stone was laid by the Bishop of the Riverina Diocese on 26 June 1954. The church was consecrated on 3 November 1974.

## Description

A simple brick church with a steeply pitched gable roof. There is a brick porch to the front elevation with a central entrance door. There is a low brick fence with decorative cast iron gate and a variety of trees and shrubs to the grounds, including a mature Lombardy poplar to the rear.

## Statement of Significance

Social significance to the Anglican community of Uranquinty and district. Local significance.

## Photograph/Plan



## Sources of Information

*Uranquinty Public School Centenary, 1880-1980*

# Wagga Wagga Heritage Study 1999

---

Name: Trinity Lutheran Church  
Address: O'Connor Street  
Town/Place Uranquinty

Reference No: URA 15  
Suburb/Locality Uranquinty

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Religion

Site Type Church

## Property Details

Map Reference Uranquinty 8327-4-S 226 054

## Historical Background

Built in 1922 by Mr Lonergan from Wagga Wagga. The land was donated by J. Kohlhagen and W. Kroker. Much of the woodwork including the altar was the work of Mr F. Siebels. Total cost of the building was £700. An electronic organ was installed in 1969 to replace the first American organ.

## Description

Simple red brick country church with a steep pitched gable roof with exposed rafters. White painted render highlights the lancet windows and buttresses and encircles the building at window sill height.

## Statement of Significance

Historical and social significance to the Lutheran community of Uranquinty and district. Local significance.

## Photograph/Plan



## Sources of Information

*Uranquinty Public School Centenary, 1880-1980*

# Wagga Wagga Heritage Study 1999

---

Name: Weatherboard cottage

Reference No: URA 16

Address: O'Connor Street

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Townships

Site Type House

Property Details

Map Reference Uranquinty 8327-4-S 228 056

Historical Background


## Description

Simple timber cottage with corrugated iron gable roof and a verandah across the front elevation.

## Statement of Significance

This timber cottage appears to be substantially intact and is a remnant of early Uranquinty township development. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Ganawarra

Reference No: URA 17

Address: Pearson Street

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Townships

Site Type House

Property Details

Map Reference

Historical Background

James & Lou Taber were amongst the first to built homes at Uranquinty. They carried out contract work and farming, settling in 1892. This was the family home of Misses Florance [1893-1976] and Elizabeth [1897-1975] Taber. The sisters earn a most affectionate chapter in the UPSC booklet for their lifelong interest and involvement in Uranquinty.


Description

Red brick residence with a corrugated iron hip roof and encircling bullnose verandah with decorative timber brackets. Attractive fence and garden.

Statement of Significance

Historical, aesthetic and social significance to the town of Uranquinty, and an attractive element in the streetscape. Local significance.

Photograph/Plan



Sources of Information

*Uranquinty Public School  
Centenary, 1880-1980*

# Wagga Wagga Heritage Study 1999

---

Name: Memorial Avenue

Reference No: URA 18

Address: Pearson Street

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

Other Names

Current Heritage Listings

Related Places

Thematic Context

Site Type

Property Details

Map Reference Uranquinty 8327-4-5

Historical Background

Avenue of White Cedars [*Melia azederach*] were planted in Pearson Street, to commemorate each soldier who went to war from Uranquinty.

Description

A row of White Cedars line the west side of Pearson Street- [northern block only].

Statement of Significance

This avenue of White Cedar trees has social significance as it was planted as a war memorial. Local significance.

Photograph/Plan



Sources of Information

*Uranquinty Public School Centenary, 1880-1980*

# Wagga Wagga Heritage Study 1999

---

Name: Uranquinty Hall

Reference No: URA 19

Address: Pearson Street

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Cultural site

Site Type Hall

## Property Details

Map Reference Uranquinty 8327-4-S 225 057

## Historical Background

Hall completed 1910 with a loan of £1200. Built by John Gray and includes stage, dressing rooms, supper room. With constant use the debt was repaid within six months. The hall has been enlarged over the years and new windows have been inserted.

## Description

Pressed metal hall with gable roof. Side walls are corrugated iron. Ripple iron to two metres, then pressed metal with a scale pattern. Interior original and very attractive with polished cypress pine stage and benches. Half timbering effect to front gable. Painted in brown and cream.

## Statement of Significance

Historical, aesthetic and social significance and an important focus for the town as a centre of recreation activities. Unusual wall detailing and intact interior. State significance.

## Photograph/Plan



## Sources of Information

*Uranquinty Public School Centenary, 1880-1980*

# Wagga Wagga Heritage Study 1999

---

Name: Uranquinty silos

Reference No: URA 20

Address: Pearson Street

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Agriculture

Site Type Silos

Property Details

Map Reference Uranquinty 8327-4-S 223 054

Historical Background

Built 1920 and received the first wheat delivery in 1920-21 season. Constructed by the Government as part of original scheme to establish grain elevator system in New South Wales. Uranquinty silo had capacity of 150 000 bushels [4050 tonnes]. Comprised workhouse, elevator and two concrete bins.

Description

Large concrete silos with corrugated elevator structure to top.

Statement of Significance

These concrete silos, were are commonly found dotted along railway lines, are the first structures associated with large-scale grain handling in the region and have a landmark quality. Local significance.

Photograph/Plan



Sources of Information

*Uranquinty Public School  
Centenary, 1880-1980*

# Wagga Wagga Heritage Study 1999

---

Name: Uranquinty school  
Address: Uranquinty Street, cnr Pearson Street  
Town/Place Uranquinty

Reference No: URA 21  
Suburb/Locality Uranquinty

---

## Other Names

## Current Heritage Listings

Related Places Uranquinty Reserve  
Thematic Context Education  
Site Type School

## Property Details

Map Reference Uranquinty 8327-4-S 227 058

## Historical Background

A new site for the school was reserved closer to the village and on the western side of the railway in 1899. A new brick school was built by Charles Hardy & Co for £419 and Williams and Bruce built a new residence for £685. These were ready for occupation in 1900.

## Description

An attractive red brick Federation era school building with a hip roof featuring half timbering to the gables. A previously encircling verandah has been partly enclosed with weatherboard. The brick chimney is well detailed and there are air vents to the roof. A most attractive school.

## Statement of Significance

Historical, aesthetic and social significance to the community of Uranquinty and district and a focus for the community. Local significance.

## Photograph/Plan



## Sources of Information

*Uranquinty Public School Centenary, 1880-1980*

# Wagga Wagga Heritage Study 1999

---

Name: Wise grave

Reference No: URA 22

Address: Uranquinty-Cross Road

Town/Place Uranquinty

Suburb/Locality Uranquinty

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Death

Site Type Burial site

## Property Details

Map Reference Uranquinty 8327-4-S 173 076

## Historical Background

Frederick Wise was an early settler in this area. When he died his family considered that Wagga Wagga was too far away for him to be buried there. The inscription on this headstone reads 'In Affectionate Remembrance/ Frederick Marryat Wise/ who departed this life May 13 1846'. Mrs Wise later remarried a Taylor and went to live in the village of Uranquinty.

## Description

A white marble gravestone with a cyclone wire surround, situated in a paddock underneath a large eucalypt. The grave is approximately 100 metres from the Uranquinty-Cross Road, at Roping Pole Swamp.

## Statement of Significance

This early settler's burial site has a poignant quality and is of historical, aesthetic and social significance to the local community. Local significance.

## Photograph/Plan



## Sources of Information

Kath McGeaghie [great great granddaughter]  
*Uranquinty Public School Centenary, 1980*

# Wagga Wagga Heritage Study 1999

---

Name: Pomingalarna Reference No: YAR 01  
Address: Sturt Highway  
Town/Place: South Wagga Wagga Suburb/Locality: Yarragundry

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context: Pastoralism

Site Type: House

## Property Details

Map Reference: Wagga Wagga 8327-1-N 256 165

## Historical Background

The first wheat crop in the district was grown on clear sandhill near Pomingalarna in 1846. It was sown by A. Marshall and B. Bennett with an old wooden plough, single furrow, drawn by four bullocks. The property was owned by the Wagga retail merchant David Copland from c1870s until the mid 20th century. Copland is believed to have built the existing house. Fire destroyed the earlier homestead in 1979.

## Description

A substantial Federation era white painted brick residence with a corrugated iron gable roof. The main entrance faces north and features a gabled entrance portico with paired tapered columns resting on a face brick dwarf wall which extends around the encircling verandah. The verandah features decorative timber fretwork brackets. Chimneys are well detailed. Detailed brick pillars support entrance gates and there are mature plantings throughout the untended garden and a stone outbuilding similar to those at nearby Moorong.

## Statement of Significance

Historical and aesthetic significance as a fine example of a substantial Federation era station residence. State significance.

## Photograph/Plan



## Sources of Information

*Uranquinty Public School Centenary, 1880-1980*  
*Daily Advertiser, 14 December 1979*  
and 10 April 1981

# Wagga Wagga Heritage Study 1999

---

Name: Yarragundry School [former]

Reference No: YAR 02

Address: Sturt Highway

Town/Place Yarragundry

Suburb/Locality Yarragundry

---

## Other Names

## Current Heritage Listings

## Related Places

Thematic Context Education

Site Type School

## Property Details

Map Reference Collingullie 8327-4-N 205 145

## Historical Background

This was formerly the Yarragundry School.

## Description

A brick former school, now in private ownership. A number of modifications have been undertaken.

## Statement of Significance

Historical and social significance to the local community. Local significance.

## Photograph/Plan

## Sources of Information

John Petterson, Yarragundry Station



# Wagga Wagga Heritage Study 1999

---

Name: Cottage and pise outbuilding

Reference No: YAR 03

Address: Sturt Highway [RMB 1009]

Town/Place Yarragundry

Suburb/Locality Yarragundry

---

Other Names

Current Heritage Listings

Related Places

Thematic Context Pastoralism

Site Type Farm complex

Property Details

Map Reference Collingullie 8327-4-N 168 155

Historical Background

## Description

A rendered brick or rendered pise cottage with a steeply pitched corrugated iron roof and an encircling bullnose verandah. To the rear there is a pise and timber outbuilding with a corrugated iron gable roof.

## Statement of Significance

Historical and aesthetic significance as an intact example of early cottage and outbuilding complex. Local significance.

## Photograph/Plan



## Sources of Information

# Wagga Wagga Heritage Study 1999

---

Name: Cottage and pise outbuilding

Reference No: YAR 03

Address: Sturt Highway [RMB 1009]

Town/Place Yarragundry

Suburb/Locality Yarragundry

---

Pise and timber outbuilding.

